

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-22399-00-00  
Spot: SENWSW Sec/Twnshp/Rge: 24-32S-4W  
1650 feet from S Section Line, 660 feet from W Section Line  
Lease Name: WEISHAAR Well #: 4-G  
County: SUMNER Total Vertical Depth: 3004 feet

Operator License No.: 32346  
Op Name: BARTELSON, MITCHEL DBA BARTELS  
Address: 118 N. ANSON RD.  
MAYFIELD, KS 67103

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2994		100 SX
SURF	8.625	409		250 SX

\$1 97.63

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/02/2006 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Sand to 2940' and 5 sxs; recover pipe; 35 sxs @ 650'; 35 sxs @ 450'; circ 250'-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 10/02/2006 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Filled hole with sand to 2902'. Hole still giving up gas. Set CIBP at 2882' and capped with 2 sacks of cement. Recovered casing from 2060'. Pulled casing to 650' and spotted 35 sacks of cement. Pulled casing to 450' and spotted 35 sacks of cement. Pulled casing to 250' and circulated cement to surface.

60/40 posmix with 4% gel

Consolidate

Perfs:

Top	Bot	Thru	Comments
3004	3007		OPEN HOLE
2994	3004		OPEN HOLE


RECEIVED  
KCC DISTRICT #2  
OCT 30 2006  
WICHITA, KS

INVOICED  
DATE 1-4-07  
INV. NO. 2007061048

Remarks:

Plugged through: CSG

District: 02

Signed   
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION-2/3

DEC 29 2006

CONSERVATION DIVISION  
WICHITA, KS

*m*

*PRT*