

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20336-00-00
Spot: SENE Sec/Twnshp/Rge: 18-31S-6E
3310 feet from S Section Line, 581 feet from E Section Line
Lease Name: WEIGLE Well #: 2
County: COWLEY Total Vertical Depth: 3000 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2805		
PROD	4.5	3000		150 SX CMT
SURF	8.625	205		150 SX CMT

\$97.50

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/23/2006 8:00 AM
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.
Proposal Rcvd. from: BRENT WHITEMAN Company: WHITEMAN, RON DBA GEN-DOR Phone: (620) 222-7808

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
OCT 25 2006
WICHITA, KS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 10/09/2006 1:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

9/23/2006 -- RIH with CIBP set at 2805'. Dump bailed 4 sacks of cement on top. Sanded back at 2400'. Dump bailed 6 sacks of cement on top.

9/25/2006 -- Shot 4-1/2" casing at 1347'. POOH with 34 jts of 4-1/2" casing.

10/9/2006 -- RIH with tubing at 350'. Gen-Dor mixed and pumped 128 sacks of 60/40 posmix with 4% gel to surface.

United Cement #7035

Perfs:

Top	Bot	Thru	Comments
2920	2928		
2516	2518		
2509	2511		
2502	2504		

INVOICED

DATE 1-4-07
INV. NO. 2007061049

Remarks:

Plugged through: TBG

District: 02

Signed Duane R. Krueger
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
FORM CP-2/3
DEC 29 2006
CONSERVATION DIVISION
WICHITA, KS

PKT