

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-041-19020-00-00  
Spot: NESESW Sec/Twnshp/Rge: 6-15S-1E  
990 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: RIORDAN Well #: 2  
County: DICKINSON Total Vertical Depth: 2578 feet

Operator License No.: 5610  
Op Name: BRUCE OIL COMPANY, L.L.C.  
Address: 1704 LIMESTONE RD.  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2578	1400	
SURF	8.625	100		\$ 83,79

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/06/2006 8:00 AM  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE, INC. Phone: (620) 628-4723

Proposed Plugging Method: Sand bottom to 50' above perfs; cap w/ 4 sxs; pull casing and set bridge at 250'; dump slurry mix to fill from 250' to surf.

Plugging Proposal Received By: GREG EVES WitnessType: NONE  
Date/Time Plugging Completed: 10/06/2006 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded bottom to 2480' and capped with 4 sacks of cement. Pulled casing and set bridge at 280'. Bailed fluids to 280'. Dumped slurry mix to fill from 280' to surface. 1400' of casing was recovered.

60/40 posmix with 4% gel & 22 sx/yd with 10% sand slurry mix

Smokey Valley #016194

Perfs:

RECEIVED  
KCC DISTRICT #2  
OCT 30 2006  
WICHITA, KS

Remarks: PLUGGED THROUGH SUFACE CASING

Plugged through: CSG

INVOICED  
DATE 1-4-07  
INV. NO. 2007061051

District: 02

Signed Meg Eves  
(TECHNICIAN)

RECEIVED Form CR 2/3  
KANSAS CORPORATION COMMISSION  
DEC 29 2006  
CONSERVATION DIVISION  
WICHITA, KS

PKT