

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20348-00-01
Spot: NENESE Sec/Twnshp/Rge: 18-31S-6E
2317 feet from S Section Line, 552 feet from E Section Line
Lease Name: WEIGLE Well #: 3
County: COWLEY Total Vertical Depth: 2982 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2760		
PROD	4.5	2977		210 SX CMT \$ 96.92
SURF	8.625	200		150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/02/2006 8:00 AM
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.
Proposal Rcvd. from: BRENT WHITEMAN Company: WHITEMAN, RON DBA GEN-DOR Phone: (620) 222-7808

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 10/09/2006 11:30 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

9/2/2006 -- RIH with CIBP set at 2760'. Dump bailed 4 sacks of cement on top. Sanded back to 2425'. Dump bailed 6 sacks of cement on top.
9/6/2006 -- Shot 4-1/2" casing at 600'. POOH with 15 jts of 4-1/2" casing.
10/9/2006 -- RIH with tubing at 350'. Gen-Dor mixed and pumped 129 sacks of 60/40 posmix with 4% gel to surface.
United Cement #7035

Perfs:

Top	Bot	Thru	Comments
2899	2913		
2505	2524		

RECEIVED
KCC DISTRICT #2
OCT 25 2006
WICHITA, KS

INVOICED

DATE 1-4-07
INV. NO. 2007061049

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

DEC 29 2006 Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS