

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-20676-00-00  
Spot: N2NESWNE Sec/Twnshp/Rge: 18-31S-6E  
3914 feet from S Section Line, 1717 feet from E Section Line  
Lease Name: WEIGLE Well #: 7  
County: COWLEY Total Vertical Depth: 2914 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2854		75 SX CMT
SURF	8.625	190		175 SX CMT

*\$94.71*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/15/2006 10:00 AM  
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.  
Proposal Rcvd. from: BRENT WHITEMAN Company: WHITEMAN, RON DBA GEN-DOR Phone: (620) 222-7808

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 10/09/2006 3:50 PM KCC Agent: DUANE KRUEGER

**Actual Plugging Report:**

9/15/2006 -- Sanded back at 2750'. Dump bailed 6 sacks of cement on top.  
9/16/2006 -- Shot 4-1/2" casing at 2040'. POOH with 48 jts of 4-1/2" casing.  
10/9/2006 -- RIH with tubing at 350'. Gen-Dor mixed and pumped 136 sacks of 60/40 posmix with 4% gel to surface.  
United Cement #7036

**Perfs:**

Top	Bot	Thru	Comments
2854	2871		

RECEIVED  
KCC DISTRICT #2  
OCT 25 2006  
WICHITA, KS

INVOICED

DATE 1-4-07  
INV. NO. 2007061049

Remarks:  
Plugged through: TBG

District: 02

Signed \_\_\_\_\_

*Duane Krueger*  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 29 2006 Form CP-2/3  
CONSERVATION DIVISION  
WICHITA, KS

*M*

*PKT*