

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-20739-00-00  
Spot: <sup>SW</sup> SWNE Sec/Twnshp/Rge: 18-31S-6E  
2663 feet from S Section Line, 2562 feet from E Section Line  
Lease Name: WEIGLE Well #: 8  
County: COWLEY Total Vertical Depth: 2933 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

| String | Size  | Depth (ft) | Pulled (ft) | Comment    |
|--------|-------|------------|-------------|------------|
| CIBP   |       | 2532       |             |            |
| PROD   | 4.5   | 2924       |             | 150 SX CMT |
| SURF   | 8.625 | 200        |             |            |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/02/2006 9:00 AM  
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.  
Proposal Rcvd. from: RON WHITEMAN Company: WHITEMAN, RON DBA GEN-DOR Phone: (620) 222-7808

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 10/09/2006 5:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

9/2/2006 -- RIH with CIBP and set at 2532'. Dump bailed 4 sacks of cement on top. Sanded back at 2375'. Dump bailed 6 sacks of cement on top.  
9/11/2006 -- Shot 4-1/2" casing at 1528'. POOH with 36 jts of 4-1/2" casing.  
10/9/2006 -- RIH with tubing at 350'. Gen-Dor mixed and pumped 137 sacks of 60/40 posmix with 4% gel to surface.  
United Cement #7036

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2804 | 2888 |      |          |
| 2469 | 2504 |      |          |

RECEIVED  
KCC DISTRICT #2  
OCT 25 2006  
WICHITA, KS

INVOICED

DATE 1-4-07  
INV. NO. 2007061049

Remarks:

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3  
DEC 29 2006  
CONSERVATION DIVISION  
WICHITA, KS

*N*

*PKT*