

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24249-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 2-34S-3E
1626 feet from S Section Line, 2076 feet from E Section Line
Lease Name: WALTON Well #: 2-1
County: COWLEY Total Vertical Depth: 3435 feet

Operator License No.: 32802

Op Name: BERT CARLSON

Address: 1432 NIGHTHAWK RD
YATES CENTER, KS 66783

String Size Depth (ft) Pulled (ft) Comment
SURF 8.625 300

\$ 111.64

Well Type: DH

UIC Docket No:

Date/Time to Plug: 09/18/2006 8:00 AM

Plug Co. License No.: 31440

Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC

Proposal Revd. from: ALBERT COOPER

Company: ALBERT COOPER

Phone: (620) 221-2377

Proposed Plugging Method: 35 SACKS AT BOTTOM THEN CEMENT TOP 350'.

RECEIVED
KCC DISTRICT #2
SEP 27 2006
WICHITA, KS

Plugging Proposal Received By: DUANE KRUEGER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/18/2006 1:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

9/18/2006 -- RIH with tubing at 3187'. Consolidated mixed and pumped 35 sacks of 60/40 posmix with 4% gel. POOH with tubing at 350'. Consolidated mixed and pumped 140 sacks of 60/40 posmix with 4% gel to surface.

9/20/2006 -- Tagged top plug at 50'. Redi Mix dumped 1 cu yd less 10% sand from 50' to surface. Well topped off.

Consolidated #10736
60/40 posmix with 4% gel

INVOICED
DATE 1-4-07
INV. NO. 2007061050

Remarks:

Plugged through: TBG

District: 02

Signed

Duane R. Krueger

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

DEC 29 2006

CONSERVATION DIVISION
WICHITA, KS

PKT