

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-041-20057-00-01  
Spot: SWSWSW Sec/Twnshp/Rge: 6-15S-1E  
272 feet from S Section Line, 5101 feet from E Section Line  
Lease Name: RIORDAN OWWO Well #: 5  
County: DICKINSON Total Vertical Depth: 2662 feet

Operator License No.: 5610  
Op Name: BRUCE OIL COMPANY, L.L.C.  
Address: 1704 LIMESTONE RD.  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2661	1800	
SURF	8.625	110		

# 8652

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/10/2006 8:00 AM  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE, INC. Phone: (620) 628-4723

Proposed Plugging Method: Sand bottom to 50' above perfs; cap w/ 4 sxs; pull casing and set bridge at 250'; dump slurry mix to fill from 250' to surf.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL  
Date/Time Plugging Completed: 10/10/2006 3:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded bottom to 2450' and capped with 4 sacks of cement. Pulled casing and set bridge at 280'. Bailed fluid to 280' and dumped slurry mix to fill from 280' to surface.  
60/40 posmix with 4% gel & 22 sx/yd with 10% sand slurry mix  
Smokey Valley #016219

Perfs:

RECEIVED  
KCC DISTRICT #2  
OCT 30 2006  
WICHITA, KS

Remarks: PLUGGED THROUGH SURFACE CASING

Plugged through: CSG

INVOICED  
DATE 1-4-07  
INV. NO. 2007061057

District: 02

Signed Greg Eves  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 29 2006  
CONSERVATION DIVISION  
WICHITA, KS

*[Handwritten signature]*

*[Handwritten signature]*