

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-041-20045-00-00
Spot: SWSESW Sec/Twnshp/Rge: 6-15S-1E *Perfs*
290 feet from S Section Line, 370 feet from E Section Line
Lease Name: RIORDAN Well #: 3
County: DICKINSON Total Vertical Depth: 2636 feet

Operator License No.: 5610
Op Name: BRUCE OIL COMPANY, L.L.C.
Address: 1704 LIMESTONE RD.
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2635	1200	180 SX CMT.
SURF	8.625	112		125 SX CMT.

\$85.67

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/10/2006 8:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE, INC. Phone: (620) 628-4723

Proposed Plugging Method: Sand bottom to 50' above perfs; cap w/ 4 sxs; pull casing and set bridge at 250'; dump slurry mix to fill from 250' to surf.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 10/10/2006 3:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded bottom to 2050' and capped with 4 sacks of cement. Pulled casing and set bridge at 260'. Bailed fluids to 260' and dumped slurry mix to fill from 260' to surface.
60/40 posmix with 4% gel & 22 sxs/yd with 10% sand slurry mix
Smokey Valley #016219

Perfs:

Top	Bot	Thru	Comments
2595	2600		

**RECEIVED
KCC DISTRICT #2
OCT 30 2006
WICHITA, KS**

INVOICED
1-4-07

Remarks: PLUGGED THROUGH SURFACE CASING.

Plugged through: CSG

DATE 1-4-07
INV. NO. 2007061051

District: 02

Signed Greg Eves
(TECHNICIAN)

m

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 29 2006
CONSERVATION DIVISION
WICHITA, KS

PET