

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19492-00-00
Spot: NENENW Sec/Twnshp/Rge: 8-28S-7E
4868 feet from S Section Line, 2977 feet from E Section Line
Lease Name: DEMOSS A Well #: 1
County: BUTLER Total Vertical Depth: 2731 feet

Operator License No.: 5387
Op Name: THE BUCKEYE CORPORATION
Address: AZTEC OIL CO. DIVISION PO BOX 102
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2649		
SURF	7	2145		

88-76

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2006 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 09/06/2006 3:45 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

7/6/2006 -- POOH with tubing and rods. Sanded back at 2595' and dump bailed 5 sacks of cement on top.

8/8/2006 -- Shot 5-1/2" casing at 1700' and 1510'. POOH with 1510' of 5-1/2" casing.

8/10/2006 -- Perforated 7" at 250'.

9/6/2006 -- RIH with 1" tubing at 250'. Braden mixed and pumped 265 sacks of 60/40 posmix with 4% gel to surface. POOH with 1" tubing. Circulated cement on backside of 7" casing. Topped off casings to surface.

Braden Petroleum #06-536

Perfs:

Top	Bot	Thru	Comments
2649	2720		

RECEIVED
KCC DISTRICT #2
SEP 27 2006
WICHITA, KS

INVOICED
DATE 1-4-07
INV. NO. 2007061052

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

DEC 29 2006

CONSERVATION DIVISION
WICHITA, KS

PFT