

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19494-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 8-28S-7E  
4869 feet from S Section Line, 4245 feet from E Section Line  
Lease Name: DEMOSS A Well #: 6  
County: BUTLER Total Vertical Depth: 2684 feet

Operator License No.: 5387  
Op Name: THE BUCKEYE CORPORATION  
Address: AZTEC OIL CO. DIVISION PO BOX 102  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD 7		2640		40 SX CMT

\$ 87.23

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/30/2006 12:00 PM  
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C  
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/23/2006 4:00 PM KCC Agent: DUANE KRUEGER

**Actual Plugging Report:**

5/30/2006 -- Tubing and packer hung up in hole.  
6/1/2006 -- RIH with wireline inside 2-3/8" tubing at 837'. Could not get any deeper.  
6/5/2006 -- Shot tubing at 835'. POOH with tubing. RIH with workover string at 800'. Braden mixed and pumped 35 sacks of class A cement.  
6/7/2006 -- Tagged cement plug at 640'. RIH with wireline at 250' and perforated 7" casing.  
6/9/2006 -- RIH with 1" tubing at 250'. Braden mixed and pumped 65 sacks of 60/40 posmix with 4% gel to surface. RIH with 1" tubing on backside of 7" casing. Braden mixed and pumped 165 sacks of 60/40 posmix with 4% gel.  
8/23/2006 -- RIH with 1" tubing on backside of 7" at 55' and circulated 135 sacks of 60/40 posmix with 4% gel to surface. Topped off from 25' to surface inside 7" casing.  
Braden Petroleum #06-534

**Perfs:**

Top	Bot	Thru	Comments
2640	2684		

**RECEIVED  
KCC DISTRICT #2  
SEP 27 2006  
WICHITA, KS**

**INVOICED**  
DATE 1-4-07  
INV. NO. 200706105

Remarks:

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

*Duane Krueger*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

DEC 29 2006

CONSERVATION DIVISION  
WICHITA, KS

*M*

*RET*