

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-01391-00-00
Spot: SENESE Sec/Twnshp/Rge: 22-20S-3W
1634 feet from S Section Line, 609 feet from E Section Line
Lease Name: SCHRAG Well #: 2
County: MCPHERSON Total Vertical Depth: 3651 feet

Operator License No.: 32778
Op Name: CAT ENERGY, LLC
Address: PO BOX 507
GALVA, KS 67443

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3650	1693	140 SX
SURF	8.625	163		125 SX

\$ 118.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/27/2006 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DUANE PURSER Company: CAT ENERGY, LLC Phone: (620) 245-9091

Proposed Plugging Method: Sand to 50' above top perms and cap with 5 sxs cmt. Pump 35 sxs @ 540'. Circ to surf from 260'.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: PARTIAL
Date/Time Plugging Completed: 11/27/2006 11:30 AM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 3020' and capped with 5 sacks of cement. Pulled pipe to 530' and pumped 35 sacks of cement. Pulled pipe to 260' and pumped 185 sacks of cement to circulate to surface.
220 sxs 60/40 posmix with 4% gel
Gressel #031267

Perfs:

RECEIVED
KCC DISTRICT #2
DEC - 5 2006
WICHITA, KS

Remarks:

Plugged through: CSG

INVOICED
DATE 1-4-07
INV. NO. 2007061054

District: 02

Signed Greg Eves
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3
DEC 29 2006
CONSERVATION DIVISION
WICHITA, KS