

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-055-00818-00-00
 Spot: ~~NW~~ ~~SE~~ ~~NW~~ ~~NW~~ Sec/Twnshp/Rge: 6-24S-31W
~~1220~~ feet from ~~N~~ Section Line, ~~3960~~ feet from E Section Line
 Lease Name: HARMS Well #: 1-6
 County: FINNEY Total Vertical Depth: 2750 feet

Per
 G.P.S
 1-7-06

Operator License No.: 32334
 Op Name: CHESAPEAKE OPERATING, INC.
 Address: PO BOX 18496 6200 N WESTERN AVE.
OKLAHOMA CITY, OK 73154

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1250		
CIBP		2600		
PROD	5.5	2748	0	WITH 300 SX CMT
SURF	8.625	325		WITH 225 SX CMT

\$ 89.38

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/02/2006 12:00 PM
 Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
 Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: RIH TO PBTD, PUMP 25 SX CMT, PLUG W/200# HULLS. POOH TO 1500', SPOT 25 SX PLUG. POOH TBG., LET CMT SET UP, PRESSURE TEST CSG TO 300 PSIG. MIRU WIRELINE, PERF@ 1200', POOH, MIRU CEMENTERS, DIG OUT BRADENHEAD, EIR DOWN 5 1/2' & PUMP 250 SX DOWN 5 1/2' CSG, TIE ONTO 5 1/2" X 8 5/8 ANNULUS, ATTEMPT TO PUMP IN. IF ABLE, PUMP 175 SX CMT. RDMO. WELD ONCAP & CLEAN LOCATION.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
 Date/Time Plugging Completed: 12/06/2006 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG SET CIBP @ 2600'. 2ND PLUG SET CIBP @ 1250' (TESTED CASING, LOCATED HOLES BETWEEN 558' & 1080'). 11/9/06: PERFORATED AT 1200', SET CMT RETAINER AT 1150'. 12/6/06: RUN 2 3/8" TUBING TO RETAINER & PUMP 35 SX CMT & 7 SX CMT ON TOP OF RETAINER. 3RD PLUG PULL TUBING TO 1000' & PUMP 45 SX CMT & 100# HULLS. 4TH PLUG PULL TUBING TO 500'. CIRCULATE CMT TO SURFACE WITH 50 SX CMT & 100# HULLS. 5TH PLUG PUMP 50 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. MAXIMUM PRESSURE 200#. 6TH PLUG TOP OFF 5 1/2" CASING WITH 5 SX CMT. TESTED TO 275# AND HELD.

Perfs:

Top	Bot	Thru	Comments
2656	2674		

INVOICED
 DATE 1-4-07
 INV. NO. 2007061055


INVOICE NO.
DATE

INVOICED

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed [Signature]

(TECHNICIAN) RECEIVED
 KANSAS CORPORATION COMMISSION
 DEC 26 2006
 CONSERVATION DIVISION
 WICHITA, KS