

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-22045-00-00
Spot: NWSW Sec/Twnshp/Rge: 6-28S-6W
1980 feet from S Section Line, 4620 feet from E Section Line
Lease Name: LAKIN Well #: 3-6
County: KINGMAN Total Vertical Depth: 3968 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	210		

\$128.96

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/28/2006 6:00 AM
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.
Proposal Rcvd. from: MIKE Company: PICKRELL DRILLING COMPANY, I Phone: _____

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: GREG EVES WitnessType: NONE
Date/Time Plugging Completed: 10/28/2006 10:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Pumped 35 sacks of cement through the drill pipe at 1150'. Pulled to 600' and pumped 35 sacks of cement. Pulled to 260' and pumped 35 sacks of cement. Pulled to 60' and circulated 25 sacks of cement to surface. Pumped 15 sacks of cement in rathole.

60/40 posmix with 4% gel

Allied #23387

Perfs:

RECEIVED
KCC DISTRICT #2
OCT 30 2006
WICHITA, KS

INVOICED
DATE 1-4-07
INV. NO. 2007061043

Remarks:

Plugged through: DP

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 29 2006

CONSERVATION DIVISION
WICHITA, KS

m

PKT