

State of Kansas



15-163-20149-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. - 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cooke of Abercrombie Drlg., Inc. has this
date requested permission to plug the following described well:

Mr. Cooke guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drlg., Inc.

Complete Address: 801 Union Center Wichita, Kansas

Lease Name: Watkins Well No. 1

Location: SE NE SW Sec. 15 Twp. 9 Rge. 17 (E)(W) XX

County: Rooks Total Depth 3572 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cooke was instructed to plug the well as follows:

Guh pits, circulate heavy mud, set cementing plug at 800' and displace
50 sc cement thru drill pipe. Heavy mud to 245' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

B. J. Massie
Conservation Division Agent