

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

October 24, 1980

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Woodrahl of Aspen Exploration, Inc. has this date requested permission to plug the following described well:

Mr. Woodrahl guarantees payment of the plugging fee.

Operator's full Name: Aspen Oil Company

Complete Address: 7701 E. Kellogg, Suite 525, Wichita, Kansas 67207

Lease Name: Westhusin "A" Well No. 1

Location: NW NE NE Sec. 15 Twp. 9 Rge. 17 (W) X

County: Rooks Total Depth 3460' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Woodrahl was instructed to plug the well as follows:

8 5/8" - 250' - circ. Fill hole with mud. Pump 50 sacks 50-50 Poz. 40 gal 2% cal ch br.
through drill pipe at 600'. Pump 40 sacks cement through
drill pipe at 255'. Fill hole with mud to 40'. Push
plug and 1/2 sack balls to 40' and cap hole with 5 sacks -
cement. Cement rat hole with 5 sacks.

STATE CORPORATION COMMISSION

10/28/80
OCT 28 1980

Very truly yours,

Alfred J. Turner
Conservation Division Agent
Wichita, Kansas