

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
12/20/76
DEC 20 1976
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Farr of Liberty Enterprises has this

date requested permission to plug the following described well:

Mr. Farr guarantees payment of the plugging fee.

Operator's full Name: Liberty Enterprises Inc.

Complete Address: Box 904, Hays, Ks.

Lease Name: McElhaney Well No. 1

Location: SW SW NE Sec. 3 Twp. 9 Rge. (E)(W) 18

County: Rooks Total Depth 3540' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Farr was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 550' thru drill
pipe. Heavy mud to 185' set 25 sk cmt plug thru drill pipe. Heavy
mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Mansley
Conservation Division Agent