

State of Kansas



RECEIVED STATE CORPORATION COMMISSION

FORM CP-2

DEC - 4 1981

State Corporation Commission CONSERVATION DIVISION Wichita, Kansas

CONSERVATION DIVISION (Oil, Gas and Water)

200 Colorado Derby Building WICHITA, KANSAS 67202

JOHN CARLIN R. C. LOUX JANE T. ROY PHILLIP R. DICK CAROL J. LARSON

Governor Chairman Commissioner Executive Secretary

RECEIVED STATE CORPORATION COMMISSION

DEC - 12/4/81

CONSERVATION DIVISION Wichita, Kansas

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Merlin Glover of Buffalo Dely Co Inc has this date requested permission to plug the following described well:

Operator's Full Name: Price Exploration Company Complete Address: 412 Mayo Bldg. Tulsa, Oklahoma 74103 Lease Name: Yanoung Well No. "A" #2 Location: C-NW-SW Sec. 32 Twp. 9 Rge. 17 (E) (W) County: Rooks Total Depth: 3621 FT. Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereafter indicated:

Mr. Glover was instructed to plug the well as follows:

8 3/8" - 258 FT SP. CUM 165# Cement - 2% Gel. - 2% Ca-Cl. Order 125# 50/50 Forming 4% Gel - 2% Ca-Cl. + 8 3/8" Plug. Spot With Drill Stem - With Heavy mud Between all plugs. 1st Plug @ 840 FT w/ 70# Cnt. 2nd Plug @ 250 FT w/ 40# Cnt. 3rd Plug - Solid Bridge - 40 FT w/ 10# Cnt. 5th In Pat Hole Very truly yours, (By Sam Cnt)

Marion Schmidt Conservation Division Agent