

15-163-01076-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
6/16/64
JUN 16 1964

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name D & D Drg Co
Complete Address: 307 Schweiter Bldg Wichita, Kansas
Lease Name Westhusin Well No. 1
Location SW SW SW Sec. 14 Twp. 9 Rge. (E) (W) 17
County Rooks Total Depth 3530
Abandoned Oil Well Gas Well Input Well SWD Well D & A x
Other well as hereafter indicated:
Plugging Contractor: same & Sun Cementing Co
Address: License No.
Operation Completed: Hour 6PM Day 13 Month 6 Year 64

The Above well was plugged as follows:

8 5/8" 228' circulated with cement.

Circulated hole with heavy mud, set plug at 550' - displaced 25 sax
cement through drill pipe - heavy mud to 220' - set plug and displaced
20 sax cement through drill pipe, heavy mud to 40', set plug, hulls
and filled to bottom cellar with cement.

Cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edwin Perry*
Well Plugging Supervisor

DATE 6/16/64
INV. NO. 937-4