

15-163-30162-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3/14/69
MAR 14 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Bennett & Roberts Oil Operations

Complete Address: Drawer 633 Russell, Kansas 67665

Lease Name Westhusin Well No. 1

Location NW SE NE Sec. 15 Twp. 9 Rge. 17 (E) (W) XX

County Rooks Total Depth ~~3468~~ 3452 ^{KCC ZAP}

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling

Address: Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 3:30P Day 10 Month 3 Year 1969

The Above well was plugged as follows:

Total Depth 3468' 8 5/8 csg set at 242' cwc

5 1/2 csg set at 3446 cw 125 sk cmt. With perf. (3419-22)

Filled 5 1/2 csg w/sd (3400-3468) Dumped 5 sk cmt w/dump bailer. (3360-3400)

Shutoff and recovered 2600' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 16 sk gel w/4 sk hulls, 100 sk 50-50 poz cmt, 6%

4 sk gel, plug and 20 sk cmt. Max. press. 200 lbs. SI pres. 200 lbs.

Cmt. (0-40) gel (40-200) Cmt. (200-640) Gel. (640-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 3/14/69
INV. NO. 9458-2