

15-163-21130-00-00

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Breck
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 -163-21,130 (of this well)

Operator's Full Name Aspen Oil Company

Complete Address 7701 E. Kellogg, Suite 575, Wichita, Kansas 67207

Lease Name Westhusin "A" Well No. 1

Location NW NE NE Sec. 15 Twp. 9 Rge. 17 (E) (W) X

County Rooks Total Depth 3460'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereafter indicated

Plugging Contractor Aspen Exploration, Inc. and Halliburton Co.

Address 7701 E. Kellogg, Suite 575, Wichita, Ks. License No.

Operation Completed: Hour 3:30A Day 25 Month October Year 1980

The Above well was plugged as follows: 8 3/8" - 250' - cem. circ.

Hole Filled with mud. 50 sacks 50/50 Pozmix - 4% gel - 2% Cal chloride
pumped through drill pipe at 600' 40 sacks Pozmix pumped
through drill pipe at 255' Hole Filled with mud to 40'
Plug and 1/2 sack hulls pushed to 40' and hole cemented
to base of cellar with 10 sacks cement. Rathole cemented
with 5 sacks.

RECEIVED
STATE CORPORATION COMMISSION
10/28/80
OCT 28 1980

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 11-19-80
INV. NO. 3619-W