

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20,903 - 00 - 00 (of this well)

Operator's Full Name Pate-Dombaugh & Martin Explorations

Complete Address 502 Union Center, Wichita, Ks.

Lease Name Westhusin Well No. 1

Location SE SW NE Sec. 15 Twp. 9 Rge. (E) (W) 17

County Rooks Total Depth 3500'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor B&B Drlg.

Address Wichita, Ks. License No.

Operation Completed: Hour 3:45 A Day 18 Month 4 Year 1979

The above well was plugged as follows:
RTD 3500' 8 5/8 csg set 208' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.
Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
4/23/79
APR 23 1979

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4-24-79
INV. NO. 9486-W

Signed: Geo Massey
Well Plugging Supervisor