

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20,771 (of this well)

Received
STATE CORPORATION COMMISSION
2/6/78
FEB 06 1978
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dreiling Oil, Inc.

Complete Address Rt #1, Victoria, Kansas

Lease Name Westhusin Well No. 1

Location 175' W of NW SE NE Sec. 15 Twp. 9 Rge. (E) (W) 17

County Rooks Total Depth 3454'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 8:30 P Day 2 Month 2 Year 1978

The above well was plugged as follows:

RTD 3454' 8 5/8 csg. set 166' cwc 125 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.

Heavy mud to 150' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2-8-78

INV. NO. 6717-W

Signed: Les Massey
Well Plugging Supervisor