

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 97-42

LOCATION C7W

SEC. 19 TWP. 18 RGE. 15 W

Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease J. Schneider "A"

Operator Shell Oil Company Address Box 744, Great Bend Mo.

Field _____ County Barton

Total Depth 3512 Feet.

Plugging Contractor Farber Casing Pulling Co.

Plugging Contractor's License No. 49

Address Great Bend Kansas.

(Describe briefly the manner in which the well was plugged)

Surface pipe 13" @ 236' c.w.c. 8 3/8" @ 923' c.w.c.
4 1/2" set 3477' w/ 100 st Cem. Baker plug set
3460' w/ 2 st Cem. top of Cem. 3438'. Shut off
and pulled 4 1/2" casing. pumped 30 st fresh
gell mud, Plug and 100 st Cem. Filling
8 3/8" surface from 300' to base of cellar
with Cem. Pumping by Halliburton

Warren H. Horner
District Conservation Agent

Date March 4, 1955

RECORDED
INDEXED
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 19 T. 18 R. 15W
BOOK PAGE 97 LINE 42