

KANSAS

*RP*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 29 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Petroleum Management, Inc.

Complete Address: 1515 Wichita Plaza, Wichita, Kansas

Lease Name Wissman Well No. # 1

Location NW NW SW Sec. 19 Twp. 18 Rge. 15 (E) (W) W

County Barton Total Depth 3450

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Same wh/Halliburton Cementing Co.

Address: Same License No.     

Operation Completed: Hour 3 P.M. Day 26 Month 2 Year 1968

The Above well was plugged as follows:

15 1/2" 223' Cwc. 10 3/4" 933' Cwc. 7" 3420'.

Replug job. Well previously plugged 1-23-'68. No pipe recovery. All records show  
7" casing Cwc. Well leaking salt water. Dug out cellar and found leak between  
7" & 10 3/4" casing. Squeezed well with 200 sack cement between 7" & 10 3/4" casing  
with Halliburton Cementing Company's pump truck, cementing from 750' to base of  
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *Don Leman*  
Well Plugging Supervisor