

15-163-20115-00-00

Form CP-3
Rev. 6-26-62



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7/11/68
JUL 11 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mallonee-Mahoney, Inc.,

Complete Address: 502 Union Center Wichita, Kansas

Lease Name Watkins Well No. 1

Location C NW NW SE Sec. 16 Twp. 9 Rge. 17 (E) (W) X

County Rooks Total Depth 3590

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Peel Bros. Inc.,

Address: Hosington, Kansas License No.

Operation Completed: Hour 9 A Day 7 Month 7 Year 1968

The Above well was plugged as follows:

RTD 8 5/8 scg at 249' cwc Cem. Mat. 100 sc 50-50 poz cem. W/6% total Gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cem.

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/12/68
INV. NO. 8092-W

Signed: Geo F. Mansy
Well Plugging Supervisor