

*B*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 06-21

LOCATION SW SW NW

SEC. 3 TWP. 9 RGE. 18

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Wildrix

Operator Cities Service Co Address Great Bend, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3374 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 286' circulated with cement - 5 1/2" at 3374' with  
175 sax cement behind - perforated at 3168' - Lane wells  
plugs at 3322' - filled with sand to 3150', set 4 sax cement  
with dump bailer - pulled 2350' 5 1/2" - filled with mud to  
286', set rock and 15 sax cement - mud to 35', set rock  
and 10 sax cement to bottom cellar.

**PLUGGING**  
WELL SEC 3 TWP 9 R 18  
BOOK PAGE 66 LINE 21

1/10/53

*Edwin P. [Signature]*  
District Conservation Agent

STATE CORPORATION COMMISSION  
Wichita, Kansas

Date 1-9-53