

15-163-30234-00-00

Form CP-3
Rev. 6-26-62

KANSAS



CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum, Inc.

Complete Address: R. R. # 2 Great Bend, Kansas 67530

Lease Name Wildrix Well No. 1

Location SW NW NW Sec. 3 Twp. 9 Rge. 18 (E) (W) X

County Rooks Total Depth 3475

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Plugging Contractor: Glenn & Smith

Address: Ellinwood, Ks. License No. 396

Operation Completed: Hour 5 P Day 20 Month 4 Year 1968

The Above well was plugged as follows:

Total Depth 3475' 8" 5/8 csg set at 213' cwc. 165 sc.

5 1/2" csg set at 3474' cw 150 sc cement.

5 1/2" PBTD 3320' and perf. (3220-26)

Filled with sand to 3200' and dumped 5 sc cement with dump bailer.

Recovered 2800' of 5 1/2" csg.

Pumped thru 8 5/8 swage with 25 sc gel W/10 sc hulls, plg and 150 sc 50-50 poz cement.

W/6% total gel. Circ. pres 300-500 lbs. SI pres 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Eric F. Massey
Well Plugging Supervisor

DATE 4/22/68

INV. NO. 7619-W

State of Kansas



15-163-30234-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67208

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1968
CONSERVATION DIVISION
Wichita, Kansas

April 12, 1968

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Wildrix
Description	SW NW NW 3-9-18W
County	Rooks
Total Depth	3475
Plugging Contractor	Glenn & Smith

Petroleum, Inc.
R. R. # 2
Great Bend, Kansas 67530

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,


J. P. Roberts, Administrator

Mr. Leo Massey # Box 582 Hays, Kansas
is hereby assigned to supervise the plugging of the above
named well.