

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23997-00-01
Spot: S2NESESE Sec/Twnshp/Rge: 25-17S-11W
790 feet from S Section Line, 330 feet from E Section Line
Lease Name: MCLEAN Well #: 2
County: BARTON Total Vertical Depth: 3684 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 200 W DOUGLAS AVE., STE 520
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3350		
PROD	7	3460	0	125
SURF	10.75	313	0	180 SX

\$ 119.73

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/06/2006 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/06/2006 11:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 3284' and dumped 5 sxs cement.
Perfed at 625' and 950'.
Ran tubing to 950' - circulated with 225 sxs 60/40 pozmix - 10% gel cement with 450# hulls.
POOH. Tied onto casing - pumped 30 sxs cement.
Max. P.S.I. 500#. S.I.P. 200#.
Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3460	3689		
3284	3285		

INVOICED
DATE 1-9-07
INV. NO. 2007061112

Remarks: COPELAND CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

Case Morris

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3
DEC 26 2006
CONSERVATION DIVISION
WICHITA, KS


DEC 21 2006

PKS

DERRICK-AMERICAN OIL, INC.
 225 N. MARKET, #330 WICHITA, KS. 67202 #2 MCLAIN SWD

25-17-11W
 130' N.
 C E/2 SE SE

CONTR LÓBO DRILLING CTY BARTON
 GEOL MARK A. THOMPSON FIELD BLOOMER



ELV 1824 KB SPD 7/5/85 CARD ISSUED 10/3/85 IP SWDW
1819 GL DRLG COMP 7/11/85 ARB OH 3460-3689

LOG	Tops	Depth	Datum
HEEB		2877-1053	
BR LM		2995-1171	
ARB		3282-1458	
GR WSH		3480-1656	
RTD		3689-1865	
<i>FSL Arb</i>		<i>603 +1781</i>	

API 15-009-23,997
 10 3/4" 313 180SX. 7" 3460 125SX
 NO CORES
 DST (1) 3271-85 (ARB) 7-45-30-45. 90' GIP. REC 390' MOY
 FROTHY OIL. 240' CL OIL. SIP 966-941#. FP 125-175 217-
 234#
 DST (2) 3271-87 (ARB) 7-45-60-45. 180' GIP. REC 720' CL
 OIL. SIP 867-883# FP 75-175 200-242#
 MICT - CO. (ARB OH). SWB DWN. NAT. SET 4 1/2" TBG AT
 3450'. SWDW - INJECTION RATE SATISFACTORY. 8 26 85

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

STATE: KANSAS COUNTY: BARTON OWWO 25-17S-11W
 FIELD: BLOOMER E2 SE SE
 OPER: VAL ENERGY 790 FSL 330 FEL SEC
 WELL: 2 MCLAIN WELL CLASS: DO ELEV: 1824 KB
 API: 15-009-23997-0001 STATUS: OIL-WO 1819 GR
 SPUD: 03/02/92 COMP: 03/03/92
 DTD: 3689 LTD: FTD: CAMBRIAN PBDT: 3350

LOC: 2 1/2 MI E CLAFLIN, KS

IP: COMP 3/3/92, IPP 30 BOPD PROD ZONE- ARBUCKLE 3284-3285 FIRST REPORT & COMPLETION

LOG TOPS:

ARBUCKLE 3264 -1440 |
 TD 3689 -1865 |

LOG TYPES NOT RPTD TBG: 2 7/8 @ 3296; DRLG COMP 03/02/92 RIG REL 03/02/92
 OWWO: OLD INFO: FORMERLY DERRICK AMERICAN OIL 2 MCLAIN SWD. SPUD
 7/5/85 10 3/4 @ 313 W/180, 7 @ 3460 W/125 SX. SPL TOPS: BROWN LIME 2995,
 ARBUCKLE 3282, CAMBRIAN 3480, OTD 3689. COMP 8/26/85. SWDW, INJ. ZN:
 CAMBRIAN 3460-3689 OH
 PERFS: (CAMBRIAN) 3460-3689 OPENHOLE, PLUG 3350 3460-3689
 PRODUCING INTERVAL: PERF (ARBUCKLE) 3284-3285 W/2 PF, NATURAL

(OVER)

COPYRIGHT 1992 PETROLEUM INFORMATION CORPORATION

DATE 05/01/92 CARD #00012-KS