

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-01089-00-00
Spot: SWNENW Sec/Twnshp/Rge: 1-30S-7W
4203 feet from S Section Line, 3751 feet from E Section Line
Lease Name: ETTA HIBBS Well #: 4
County: KINGMAN Total Vertical Depth: 4190 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PARKWAY, BLDG
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4118		
PROD	5.5	4169		125 SX
SURF	8.625	268		255 SX

\$ 136.18

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/08/2006 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Perfs @ 4108'-4114' & 4122'-4125'
Plugging PBTD 4118'
Method: Sand to 4050' w/ 5 sxs cmt
35 sxs @ 1200'
35 sxs @ 700'
circ cmt 320'-0'

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: PARTIAL
Date/Time Plugging Completed: 12/08/2006 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Sanded to 3950' and 5 sacks of cement. Recovered pipe from 2100'. Pulled to 1200' and spotted 35 sacks of cement. Pulled casing to 700' and spotted 35 sacks of cement. Pulled casing to 320' and circulated cement to surface.

60/40 posmix with 4% gel

Allied Cement

Perfs:

Top	Bot	Thru	Comments
4122	4125		
4108	4114		

RECEIVED
KCC DISTRICT #2

DEC 13 2006

WICHITA, KS

INVOICED
DATE 1-9-07
INV. NO. 200706113

Remarks:

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

DEC 29 2006

CONSERVATION DIVISION
WICHITA, KS

PREY