

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

Operator License No.: 5116
Op Name: WELLWIN DRILLING CORPORATION
Address: 201 W HARVEY AVE P.O. BOX 529
WELLINGTON, KS 67152

API Well Number: 15-035-21091-00-01
Spot: NWSW per CP213 Sec/Twnshp/Rge: 19-32S-5E
1993 feet from S Section Line, 5037 feet from E Section Line
Lease Name: ANDES Well #: 1
County: COWLEY Total Vertical Depth: 3130 feet

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		2350		
PROD	4.5	3120		
SURF	8.625	200		

\$ 101.73

Well Type: SWD UIC Docket No: D23861.0 Date/Time to Plug: 09/22/2006 10:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed See actual report.
Plugging Method:

Plugging Proposal Received By: DUANE KRUEGER
Date/Time Plugging Completed: 09/29/2006 2:40 PM

WitnessType: PARTIAL
KCC Agent: DUANE KRUEGER

Actual Plugging Report:

9/22/2006 -- MIRU. POOH with tubing and packer. Cellar work.

9/27/2006 -- Sanded back at 2350'. Dump bailed 5 sacks of cement on top. Shot 4-1/2" at 1445'.

9/28/2006 -- POOH with 34 jts of 4-1/2" casing.

9/29/2006 -- RIH with tubing at 250'. Braden mixed and pumped 100 sacks of 60/40 posmix with 4% gel to surface.

Cement ticket #06/540

Perfs:

Top	Bot	Thru	Comments
2409	2413		

RECEIVED
KCC DISTRICT #2
OCT 25 2006
WICHITA, KS

INVOICED
DATE 1-9-07
INV. NO. 2007061115

Remarks:

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3
DEC 29 2006

CONSERVATION DIVISION
WICHITA, KS

PK