

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-121-20056-00-00  
Spot: NENENW Sec/Twnshp/Rge: 9-17S-25E  
5105 feet from S Section Line, 3040 feet from E Section Line  
Lease Name: ROGERS Well #: 18  
County: MIAMI Total Vertical Depth: 400 feet

Operator License No.: 32272

Op Name: CAPTAIN'S OIL INC.

Address: 30805 COLD WATER RD.  
LOUISBURG, KS 66053

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	400		
SURF	7	20		

\$ 35.00

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/17/2005 8:00 AM

Plug Co. License No.: 32272

Plug Co. Name: CAPTAIN'S OIL INC.

Proposal Recd. from: BOB EBERHART

Company: CAPTAIN'S OIL INC.

Phone: (913) 837-2823

Proposed FILL WELL WITH 60/40 POZ MIX, TD TO SURFACE.

Plugging  
Method:

Plugging Proposal Received By: FRANK GUILFOYLE

WitnessType: NONE

Date/Time Plugging Completed: 11/20/2005 12:00 PM

KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

Perfs:

RAN 1" TO 400', PUMPED 15 SACKS OF 60/40 POZ MIX. PULLED PIPE. FILLED  
CASING WITH WATER AND PERFORATED AT 200', RAN 1" TO 250' INSIDE CASING.  
PUMPED MIX TO SURFACE INSIDE AND OUTSIDE CASING. PULLED PIPE AND  
TOPPED OFF WELL. PUMPED 60 SACKS WELL HAD 2" ON PACKER AT 100'.  
PERFORATED 2" AT 95', HOOKED ONTO 2" AND PUMPED 5 SACKS TO SURFACE.  
PUMPED TOTAL OF 80 SACKS OF POZ MIX. WELL PLUGGED.

RECEIVED  
KCC DISTRICT #3  
DEC 28 2006 *Sh*  
CHANUTE, KS

INVOICED  
DATE 1-10-07  
INV. NO. 2007061127

RECEIVED

JAN 03 2006

KCC WICHITA

Remarks: OPERATOR PLUGGED WELL.

Plugged through:

District: 03

Signed Frank GUILFOYLE *by Sh*  
(TECHNICIAN)