

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
September 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Vess Oil Corporation  
Address: 8100 E. 22nd. St. N. #300 Wichita, Ks. 67228  
Phone: ( ) Operator License #: 5030 *Per*  
Type of Well: Oil *KCC Per RBDMS Per* Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Richard Lacey (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 185-30,038 -00-00 *KCC Per 1-9-07 Per RBDMS*  
Lease Name: Bauer Nolte  
Well Number: 3  
Spot Location (OOQQ): SE - NW - SW  
2310 Feet from \_\_\_\_\_ North /  South Section Line  
4290 Feet from  East / \_\_\_\_\_ West Section Line  
Sec. 7 Twp. 21 S. R. 12 East  West  
County: Stafford  
Date Well Completed: 3-7-65  
Plugging Commenced: 12-8-06  
Plugging Completed: 12-12-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)			
Formation	Content	From	To	Size	Put In / Pulled Out
				8-5/8"	265' / None
				5-1/2"	3584' / <i>2100' 2108' per 12/3</i>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged off bottom with sand to 3240' and 5 sacks cement. Cut casing loose @2100', pulled up to 690', pumped 10 sxs. gel & 50 sxs. cement, pulled up to 290', pumped 50 sxs. cement, pulled up to 40', circulated 25 sxs. cement to surface, 60/40 pos, 6% gel.

Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529 **RECEIVED**  
Address: P.O. Box 467 Chase, Kansas 67524 **KANSAS CORPORATION COMMISSION**  
Name of Party Responsible for Plugging Fees: Vess Oil Corporation **DEC 29 2006**  
State of Kansas County, Rice ss. **CONSERVATION DIVISION WICHITA, KS**


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *Mike Kelso*  
(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 26th day of December, 20 06

*Irene Herzberg*  
Notary Public

My Commission Expires: \_\_\_\_\_



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Per*