

**Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.**

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: **CAPTAINS OIL INC.**

Address: **30805 COLDWATER RD. LOUISBURG KS. 66053**

Phone: **(913) 837 - 2823** Operator License #: **32272**

Type of Well: **OIL**

(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) Docket #: \_\_\_\_\_  
(If SWD or ENHR)

The plugging proposal was approved on: **06/01/2005** (Date)

by: **FRANK GUILFOYLE** (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

**PERU** Depth to Top: **380** Bottom: **390** T.D. **400**

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: **15-121-20056-00-00**

Lease Name: **ROGERS**

18

Well Number: **18**

Spot Location (QQQQ): **W-E - N-E - N-W - S-E**

**5105**

Feet from  North /  South Section Line

**3040**

Feet from  East /  West Section Line

Sec. **9**

Twp. **17** S. R. **25**  East  West

County: **MIAMI**

**UNKNOWN**

Date Well Completed: **NOVEMBER 2005**

Plugging Commenced: **NOVEMBER 2005**

Plugging Completed: **NOVEMBER 2005**

Show depth and thickness of all water, oil and gas formations.

<i>Oil, Gas or Water Records</i>		<i>Casing Record (Surface Conductor &amp; Production)</i>				
Formation	Content	From	To	Size	Put In	Pulled Out
<b>PERU</b>	<b>OIL</b>	<b>0</b>	<b>20</b>	<b>7</b>		
		<b>0</b>	<b>400</b>	<b>4 1/2</b>		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

**RAN 1" TO 400' SPOTTED 15 SACKS CEMENT & PULLED OUT. FILLED WELL WITH WATER ,RAN IN & SHOT 2 HOLES**

**IN CASEING AT 200". RAN 1" TO 250' PUMPED 60 SACKS CEMENT TO CIRCULATE TO SURFACE**

**INSIDE AND OUT OF CASEING. WELL HAD 2" ON A PACKER AT 100', SHOT 2" AT 95'. HOOKED ON 2" AND PUMPED**

**5 SACKS TO SUFACE. TOTAL SACKS USED TO PLUG WELL 80**

**RECEIVED**

Name of Plugging Contractor: **CAPTAINS OIL INC** License #: **32272**

Address: **30805 COLDWATER RD LOUISBURG KS. 66053** JAN 03 2006

Name of Party Responsible for Plugging Fees: **BOB EBERHART** KCC WICHITA

State of **KANSAS** County, **MIAMI**, ss.

**BOB EBERHART** (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature)

*Bob Eberhart*

(Address) **30805 COLDWATER RD. LOUISBURG KS. 66053**

**RENEE PAGE**

My Appt. Exp. **10-23-08**

Subscribed and Sworn to before me this **6th** day of **December**, 2005

My Commission Expires: **10-23-08**

Notary Public

*St. of KS County of Miami*

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202