

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Barracuda Operating Co.

Address: P.O. Box 405 Ness City, Kansas 67560

Phone: (785) 798-3122 Operator License #: 33593

Type of Well: Oil Percap213 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Michael Maier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-135-21, 201 ^{60-00 E CC} ^{PKT}

Lease Name: Hardman "A" ^{Per RBPMS}

Well Number: 1 ¹⁻⁹⁻⁰⁷

Spot Location (OQQQ): _____ C _____ NW _____ SW

660 Feet from North / South Section Line ^{Per}

660 Feet from East / West Section Line ^{CPS}

Sec. 3 Twp. 18 S. R. 25 East West ^{PKT}

County: Ness

Date Well Completed: 6-21-76 ^{Per RBPMS}

Plugging Commenced: 12-8-06

Plugging Completed: 12-12-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	310'	None
				4-1/2"	4276'	1313'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 4220' and 4 sxs. cement, Set bridge plug @1400' with 1 bbl. sand and 3 sxs. cement on top. Cut casing loose @1313', pulled up to 1100', pumper 10 sxs. gel & 80 sxs. cement, pulled up to 650', pumped 50 sxs. cement, pulled up to 320', pumped 50 sxs. cement, circulated 15 sxs. from 40' to surface. 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529 ^{RECEIVED}

Address: P.O. Box 467 Chase, Kansas 67524 ^{KANSAS CORPORATION COMMISSION}

Name of Party Responsible for Plugging Fees: Barracuda Operating Company ^{DEC 29 2006}

State of Kansas County, Rice ss. ^{CONSERVATION DIVISION WICHITA, KS}

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 26th day of December, 2006

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT