

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21483-00-00
Spot: NWNE Sec/Twnshp/Rge: 3-33S-19W
710 feet from N Section Line, 2030 feet from E Section Line
Lease Name: WEBSTER Well #: 3-2
County: COMANCHE Total Vertical Depth: 3512 feet

Operator License No.: 33770
Op Name: ARES ENERGY, LTD
Address: 303 W. WALL, SUITE 900
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	50		
SURF	8.625	497		WITH 220 SX CMT \$114.14

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/18/2006 6:00 PM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: RICK SMITH Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: 1ST PLUG AT 990' WITH 50 SX CMT. 2ND PLUG AT 520' WITH 50 SX CMT. 3RD PLUG AT 220' WITH 30 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 12/18/2006 8:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CONDUCTOR CAME UP HOLE. WASHED OUT UNDER RIG, COMPANY DUMPED ROCK & CMT IN WASH OUT. 1ST PLUG AT 990' WITH 50 SX CMT. 2ND PLUG AT 520' WITH 50 SX CMT. 3RD PLUG AT 220' WITH 30 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:


INVOICED
DATE 1-11-07
INV. NO. 2007061163

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: DP

RECEIVED
JAN 03 2006
KCC WICHITA

District: 01



Signed Eric MacLaren
(TECHNICIAN)

Form C-27