

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21700-00-00
Spot: S2NWNW Sec/Twnshp/Rge: 7-23S-11W
660 feet from N Section Line, 990 feet from W Section Line
Lease Name: FSI Well #: 5
County: STAFFORD Total Vertical Depth: 3734 feet

Operator License No.: 31327
Op Name: PAULEY, GARY DBA PAULEY OIL
Address: PO BOX 163
HOLYROOD, KS 67450

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3734	0	WITH 175 SX CMT
SURF	8.625	406		WITH 285 SX CMT #121-36

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/19/2006 9:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: GARY PAULEY Company: PAULEY OIL Phone: (785) 252-3286

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/19/2006 11:20 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

RAN TUBING TO 3200' & PUMP 50 SX CMT. DISPLACED TO 2500'. PERFORATED AT 600'. PULLED TUBING TO 620'. PUMPED 235 SX CMT DOWN TUBING. CIRCULATED CMT UP 4 1/2" & 8 5/8" X 4 1/2" ANNULUS. PULLED TUBING OUT. TOPPED OFF 4 1/2" & 8 5/8" X 4 1/2" ANNULUS WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3488			
3410			
3359			

INVOICED
DATE 1-11-07
INV. NO. 200 1061173


RECEIVED
JAN 03 2006

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID.

KCC WICHITA

Plugged through: TBG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

PKT