

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-01974-00-00
Spot: SW Sec/Twnshp/Rge: 25-23S-14E
75 feet from S Section Line, 3960 feet from E Section Line
Lease Name: HURST Well #: W 1
County: WOODSON Total Vertical Depth: 556 feet

Operator License No.: 31280
Op Name: BIRK, BRIAN L. DBA BIRK PETROLEU
Address: 874 12TH RD SW
BURLINGTON, KS 66839

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	515	0	
SURF	7	20	0	

\$ 35.00

Well Type: SWD UIC Docket No: D09692.0 Date/Time to Plug: 12/18/2006 11:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: BRIAN BIRK Company: BIRK PETROLIUM Phone: (620) 364-5875

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 515' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 4 1/2" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/18/2006 3:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS WASHED INTO THE 4 1/2" CASING TO 475'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 4 1/2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED
KCC DISTRICT #3

JAN 3 2007 CPT

CHANUTE, KS

INVOICED
DATE 1-16-07
INV. NO. 2007061183

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 08 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel
(TECHNICIAN)

PPT