

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: JOHNSON OIL

Address: 258 east highway 36 Phillipsburg Kansas 67661

Phone: (785) 543-6171 Operator License #: 3077

Type of Well: OIL Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: Aug 2 2006 (Date)

by: HERB DEINES (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

3476-3568 LANSING Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
KANSAS CITY Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 147-20,029 - 00-00

Lease Name: Faubion

Well Number: 1

Spot Location (QQQQ): se ne nw - \_\_\_\_\_ - \_\_\_\_\_  
4290 Feet from  North /  South Section Line

2970 Feet from  East /  West Section Line

Sec. 6 Twp. 2 S. R. 18  East  West

County: Phillips county kansas

Date Well Completed: 4-11-1968

Plugging Commenced: 9-20-2006

Plugging Completed: 9-20-2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	216	8 5/8	216	0
		0	3662	4 1/2	3662	0
		0	3437	2 inch	3437	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

ordered 105 sx common cement swabbed tubing dry 3437  
ran 1inch pvc pipe between 8 5/8 and 4 1/2 casing tagged cement at 50 feet pumped down 1inch pipe until cement  
circulated 12 sacks then pumped 54 sx cement down 2 inch tubing hole filled with cement . plugging complete.


Name of Plugging Contractor: allied cementing License #: 99996

Address: russell ks

Name of Party Responsible for Plugging Fees: kevin johnson

State of phillips County: kansas, ss.

sworn on oath says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Handwritten Signature]

(Address) 258 east highway 36 phillipsburg kansas 67661

SUBSCRIBED and SWORN TO before me this 21st day of December, 2006

Beverly A. Schemper My Commission Expires: March 22, 2009  
(Notary Public)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 26 2006  
CONSERVATION DIVISION  
WICHITA, KS

PCT