

LEASE NAME Conkright C

WELL NUMBER #1

3519 Ft. from S Section Line

4516 Ft. from E Section Line

SEC. 27 TWP. 16S RGE. 25W (X) or (W)

COUNTY Ness

Date Well Completed 1977 9/4/73

Plugging Commenced 12/15/06

Plugging Completed 12/15/06

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

per OPS KCCPT on
AS SWINW
AS SWINW

LEASE OPERATOR Palomino Petroleum, Inc

ADDRESS 4924 SE 84th St, Newton, KS 67114

PHONE (316) 799-1000 OPERATORS LICENSE NO. 30742

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

A plugging proposal was approved on 12/14/06 (date)

Eric MacLaren (KCC District Agent's Name).

ACO-1 filled? _____ If not, is well log attached? _____

Producing Formation Miss/Fort Scott Depth to Top _____ Bottom _____ T.O. 4510

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	<u>Surf Prod</u>		<u>303</u>	<u>8.625</u>		
			<u>4500</u>	<u>5.50</u>		
					<u>per OPS 13</u>	
					<u>PLT</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material is used, state the character of same and depth placed, from _____ feet to _____ feet each set.
12/14/06 Tried to pull stretch on casing, could not get 5 1/2' out of slips. 12/15/06 Ran 2 3/8" tubing to 4400' & spotted 20 sks standard cement w/1 sk hulls on bottom. Pulled tubing to 2000' & spotted 20 sks 3% cc, pulled tubing out of well. Perforated 5 1/2' @ 1150' & pumped 100 sks. Mix another 100 sks along w/3 sks hulls. Cement still 1000' down, wait for cement to set. Pumped 40 sks down 8 5/8. Mix 50 more sks & pump down 5 1/2'. Casing still will not top off. Mix up 110 sks, pumped down 5 1/2' & finally topped off. Job complete.

License No. 31627


Address Whitetail Crude, Inc., P O Box 544, Ness City, KS 67560-0544

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Palomino Petroleum, Inc

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President of Whitetail Crude, Inc (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts herein stated, and matters herein contained and the log of the above-described well as filled thereon are true and correct, so help me God.

(Signature) Mike J. Fritzler
(Address) P O Box 544, Ness City, KS 67560-0544



SUBSCRIBED AND SWORN TO before me this 21st day of December, 2006, X

Debra Kerr
Notary Public

My Commission Expires: 4/20/09

USE ONLY ONE SIDE OF EACH FORM

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 26 2006

CONSERVATION DIVISION
WICHITA, KS

Form 0-4
Revised 05-88

PLT