

LEASE NAME Snider

WELL NUMBER #1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

13201356 Ft. from S Section Line

W2W2SW 4950 4886 west E
 Ft. from ~~X~~ Section Line

LEASE OPERATOR Blue Goose Drilling Co Inc

SEC. 35 TWP. 16S RGE. 30W (X or (W))

ADDRESS P O Box 1413, Great Bend, KS 67530

COUNTY Lane

PHONE: (620) 792-5633 OPERATORS LICENSE NO. 5104

Date Well Completed 11/14/88 spud

Character of Well oil

Plugging Commenced 12/12/06

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12/12/06

A plugging proposal was approved on 12/12/06 (date)

Eric MaClaren (KCC District Agent's Name).

ACQ-1 filled? yes If not, is well log attached? _____

Producing Formation Lansing/Kansas City Depth to Top _____ Bottom _____ T.O. 4571

Now depth and thickness of all water, oil and gas formations. PBD 4428

WATER, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	<u>Surf Prod</u>		<u>221'</u>	<u>8.625</u>		
			<u>4244'</u>	<u>4.500</u>		
				<u>Per CPD/3 PPT</u>		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Ran tubing to 2666' & touched fish in hole. pulled 1 it & pumped 25 sks cement @ 2635' Pulled tubing to 2150' & pumped 90 sks. well went on vacuum. pulled tubing to 1200' & waited for cement to set. Pumped 15 sks cement down 8 5/8 & pressured up. Mix 70 sks cement & 500# hulls. pump down tubing @ 1200'. Pulled tubing from well. Cement was down 120'. topped off 4 1/2" casing w/50 sks cement. Job complete


Name of Plugging Contractor Swift Service Inc License No. 32382
Whitetail Crude, Inc 31627

Address P O Box 544, Ness City, KS 67560-0544

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Blue Goose Drilling Co Inc

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President of Whitetail Crude, Inc (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts contained, and matters herein contained and the log of the above-described well as filed. The same are true and correct, so help me God.



(Signature) Mike J. Fritzler
 (Address) P O Box 544, Ness City, KS 67560-0544

SUBSCRIBED AND SWORN TO before me this 21st day of December, 2006, xxx

Debra Kerr
 Debra Kerr Notary Public

My Commission Expires: 4/20/09

USE ONLY ONE SIDE OF EACH FORM

RECEIVED
 KANSAS CORPORATION COMMISSION Form CP-1
 Revised 05-88

DEC 26 2006

CONSERVATION DIVISION
 WICHITA, KS

PK9