

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-22044-00-00  
Spot: SWNWSW Sec/Twnshp/Rge: 1-30S-7W  
1577 feet from S Section Line, 5062 feet from E Section Line  
Lease Name: REIDA Well #: 5  
County: KINGMAN Total Vertical Depth: 4202 feet

Operator License No.: 5123  
Op Name: PICKRELL DRILLING COMPANY, INC.  
Address: 100 SOUTH MAIN - SUITE 505  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4198		160 SX CMT.
SURF	8.625	261		200 SX CMT

*\$ 136.57*

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/06/2006 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PBTD 4160'; perfs 4096'-4106'; sand to 4050' and 4 sxs; 35 sxs @ 1100'; 35 sxs @ 650'; circ 300'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/06/2006 10:30 AM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

The perforations were covered with sand to 4046' and 4 sacks of cement. Recovered 3050' of 4-1/2" casing. Pulled casing to 1100' and spotted 35 sacks of cement. Pulled casing to 650' and spotted 35 sacks of cement. Pulled casing to 300' and circulated cement to surface.

60/40 posmix with 4% gel

Allied #24842

**Perfs:**

Top	Bot	Thru	Comments
4096	4106		

**RECEIVED  
KCC DISTRICT #2  
OCT 30 2006  
WICHITA, KS**


**INVOICED**  
DATE 1-8-07  
INV. NO. 2007061087

Remarks:

Plugged through: CSG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

**RECEIVED  
KANSAS CORPORATION COMMISSION**

**DEC 29 2006**

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS

