

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-01150-00-00

Spot: NENENE

Sec/Twnshp/Rge: 9-19S-2W

4943 feet from S Section Line,

567 feet from E Section Line

Lease Name: MIDDLESWARTZ

Well #: 1

County: MCPHERSON

Total Vertical Depth: 2962 feet

Operator License No.: 5517 •

Op Name: RATZLAFF, STEVEN

Address: 1429 24TH AVE.
GALVA, KS 67443

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5	2943		
SURF	8	160		

96.27

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/06/2006 11:00 AM

Plug Co. License No.: 6819

Plug Co. Name: SCOTT'S WELL SERVICE INC

Proposal Rcvd. from: JAY SCOTT

Company: SCOTT'S WELL SERVICE INC

Phone: (785) 366-0392

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER

WitnessType: PARTIAL

Date/Time Plugging Completed: 12/06/2006 11:30 AM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

This well had had multiple squeeze jobs in the past; a Halliburton ticket #185464 from 1991 indicated casing had been perforated at 450' and pumped 150 sacks of cement circulated. Did run a sand pump on sand line down to 2910' where operator had already sanded and pulled out with pieces of cement on the end of the pump. Set bridge at 400' and filled 5" casing with cement. Ran 1' down backside to approximately 150' where firm cement was encountered. Pumped backside full of cement.

McPherson Slurry Mix #55804

RECEIVED
KCC DISTRICT #2
DEC 13 2006
WICHITA, KS

Remarks: PULLED THROUGH CASING AND TUBING

Plugged through: CSG

INVOICED
DATE 1-8-07
INV. NO. 2007061096

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 29 2006
CONSERVATION DIVISION
WICHITA, KS

M

PK