

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-20090-00-00  
Spot: NWSW Sec/Twnshp/Rge: 7-35S-29W  
1980 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: ADAMS RANCH Well #: 1  
County: MEADE Total Vertical Depth: 6288 feet

Operator License No.: 30604  
Op Name: RAYDON EXPLORATION, INC.  
Address: 9400 N. BROADWAY #400  
OKLAHOMA CITY, OK 73114

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	13.38	328		WITH 350 SX CMT
PROD	4.5	6282	2420	WITH 100 SX CMT
SURF	8.625	1224		WITH 650 SX CMT

\$ 204.36

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/05/2006 9:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Revd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 25 SX CEMENT THRU TUBING AT 5808" ( TOP OF JUNK AT 5900"). TRIP OUT OF HOLE WITH TUBING, SHOOT OFF CASING AT +5000', lay down casing, holes in casing from 2967'- 3030', TRIP IN HOLE WITH TUBING TO 1270', PUMP 50 SX PLUG, LAY DOWN TUBING TO 500', PUMP 40 SX PLUG, LAY DOWN TUBING TO 40'. PUMP 15 SX PLUG.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/05/2006 1:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

1ST PLUG PUMP 50# HULLS WITH 25 SX CMT AT 5800'. 2ND PLUG AT 1250' WITH 50 SX CMT. 3RD PLUG AT 500' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
6282	6288		
6250	6290		
6052	6060		

**INVOICED**  
DATE 1-8-07  
INV. NO. 2007061097

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01



Signed Jim Holland PRT III

(TECHNICIAN)  
**RECEIVED**  
KANSAS CORPORATION COMMISSION Form CP-23  
DEC 26 2006  
CONSERVATION DIVISION  
WICHITA, KS

*PKT*