

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-30164-00-01
Spot: SWNESWSE Sec/Twnshp/Rge: 16-16S-10W
688 feet from S Section Line, 1787 feet from E Section Line
Lease Name: KOZISEK A OWWO Well #: 1
County: ELLSWORTH Total Vertical Depth: 3865 feet

Operator License No.: 30458
Op Name: RJM COMPANY
Address: PO BOX 256
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3508		
SURF	8.625	290		

125.61

Well Type: SWD UIC Docket No: D16099.0 Date/Time to Plug: 11/02/2006 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/06/2006 9:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

3" tubing was stuck; perforated at 3300'. Ran 1" tubing inside of 3" to 3300' and pumped 75 sacks of hot cement. Let set for 2 hours and ran tubing down to tag, but never tagged. Pumped another 75 sacks of hot cement. Let set for 1-1/2 hours and ran tubing down to re-tag, but never tagged. Pumped another 50 sacks of hot cement. Let set overnight. Tagged with sandline on 11/3/2006 at 2750'. Perforated at 1350' and 1000'. Ran 1" tubing to 1350' and pumped 35 sacks of cement. Pulled tubing to 1000' and pumped 35 sacks of cement. Let set 1-1/2 hours. Tried to retag with sandline and swabbing rod, but failed to tag. Ran 1" tubing back down to 1350'; ready for next day.

On 11/4/2006, discovered that the 1" was cemented in the hole. Pulled on the 1" and parted at 512'. Ran 1" back down to 500' and circulated cement to surface. Connected on to 3" tubing and pumped 25 sacks of cement at 300 psi.

Rechecked on 11/6/2006 and topped off with 10 more sacks of cement.

60/40 posmix with 4% gel

Copeland #C01327
Log Tech #4734

Perfs:

RECEIVED
KCC DISTRICT #2
NOV - 8 2006
WICHITA, KS

INVOICED
DATE 1-8-07
INV. NO. 2007061099

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

M

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3
DEC 29 2006
CONSERVATION DIVISION
WICHITA, KS

PKT