

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-21950-00-00

Spot: SE

Sec/Twnshp/Rge: 22-26S-18E

1980 feet from S Section Line, 1650 feet from E Section Line

Lease Name: CANNON

Well #: SWI 1

County: ALLEN

Total Vertical Depth: 849 feet

Operator License No.: 5488 •

Op Name: TWM PRODUCTION CO., A GENERAL P

Address: 1150 HWY 39  
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	849	0	
SURF	7	21	0	

\$ 35.00

Well Type: EOR

UIC Docket No: E19590.1

Date/Time to Plug: 10/17/2006 12:00 PM

Plug Co. License No.: 5491

Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP

Proposal Rcvd. from: MIKE WIMSET

Company: W % W PRODUCTION CO.

Phone: (620) 431-5970

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO 849' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: NONE

Date/Time Plugging Completed: 10/17/2006 5:00 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 800 PSI. 52 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
758	798	CSG	

RECEIVED  
KCC DISTRICT #3  
DEC 13 2006 CPT  
CHANUTE, KS

INVOICED  
DATE 1-5-07  
INV. NO. 2007061063

Remarks:

Plugged through: CSG

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

RECEIVED  
DEC 18 2006  
KCC WICHITA

PT