

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-05682-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 33-19S-9W
3640 feet from S Section Line, 2481 feet from E Section Line
Lease Name: DEWITT Well #: 4
County: RICE Total Vertical Depth: 3227 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.625	3186		
SURF	10.63	217		

104-88

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/27/2006 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/27/2006 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Attempt to run tubing to TD and found casing was parted at 1036'. Pulled out 293' of 6-5/8" casing. Ran tubing down to 1174' outside of casing and pumped 50 sacks of cement with 300 lbs of cotton hulls. Pulled tubing to 850' and pumped 50 sacks of cement. Pulled tubing to 350' and circulated cement to surface.

60/40 posmix with 4% gel
Jet Star #15330
Used 400 sacks of cement

Perfs:

RECEIVED
KCC DISTRICT #2
DEC 13 2006
WICHITA, KS

INVOICED
DATE 1-8-07
INV. NO. 2007061091

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 29 2006
CONSERVATION DIVISION
WICHITA, KS

Handwritten mark

Handwritten mark