

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23115-00-01
Spot: NWSWSW Sec/Twnshp/Rge: 34-29S-5E
1129 feet from S Section Line, 5039 feet from E Section Line
Lease Name: TAYLOR OWWO Well #: 5
County: BUTLER Total Vertical Depth: 2870 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 125 N. MARKET ST. SUITE 1120
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2865		70 SX CMT.
SURF	8.625	205		140 SX CMT. <i>H 93.28</i>

Well Type: EOR UIC Docket No: E26050.1 Date/Time to Plug: 09/18/2006 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: REMOVE CASING ABOVE 1400' AND PLUG WELL AS PER KCC INSTRUCTIONS.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 09/19/2006 4:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

9/18/2006 -- Sanded back to 2750' and dump bailed 4 sacks of cement on top.
9/19/2006 -- Cut 4-1/2" casing at 1440'. POOH with 31 jts of 4-1/2" at 250'. United Cementing mixed and pumped 95 sacks of 60/40 posmix with 4% gel to surface. POOH with 7 jts of 4-1/2" casing and topped well to surface with cement.
United Cement #7352
60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
2806	2865		

RECEIVED
KCC DISTRICT #2
SEP 27 2006
WICHITA, KS

INVOICED
DATE 1-8-07
INV. NO. 2007061094

Remarks:

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3
DEC 29 2006
CONSERVATION DIVISION
WICHITA, KS

m

PKS