

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-21212-00-01
Spot: W2NWSE Sec/Twnshp/Rge: 6-33S-6E
2037 feet from S Section Line, 2424 feet from E Section Line
Lease Name: HAMMER Well #: 1
County: COWLEY Total Vertical Depth: 3141 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 125 N. MARKET ST. SUITE 1120
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3105	1010	75 SX
SURF	8.625	157	Percep 4 KCC PRT 1/5/06	85 SX

Well Type: EOR UIC Docket No: E20670.1 Date/Time to Plug: 09/20/2006 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTRYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: REMOVE CASING ABOVE 1600' AND PLUG WELL AS PER KCC INSTRUCTIONS.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/20/2006 3:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

9/20/2006 -- Sanded back at 2990' and dump bailed 4 sacks of cement on top. Cut casing at 1010'. POOH with 20 jts of 4-1/2" casing at 350'. United Cementing mixed and pumped 133 sacks of 60/40 posmix with 4% gel to surface. POOH with 10 jts of 4-1/2" casing and topped well off with cement.

United Cement #7246
60/40 posmix with 4% gel

Perfs:

RECEIVED
KCC DISTRICT #2
SEP 27 2006
WICHITA, KS

INVOICED
DATE 1-8-07
INV. NO. 2007061094

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3
DEC 29 2006
CONSERVATION DIVISION
WICHITA, KS

RA