

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-32677-00-00
Spot: NWNESE Sec/Twnshp/Rge: 26-12S-22W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: OGALLAH UNIT Well #: 5-2
County: TREGO Total Vertical Depth: 4034 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		1768		
PROD	5.5	4004	0	180 SX
SURF	8.625	325	0	225 SX

\$ 131.11

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/11/2006 4:30 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-2540

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/11/2006 7:45 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 2600' - pumped 150 sxs 60/40 pozmix - 10% gel cement with 400# hulls.
Pulled to 1500' - circulated with 100 sxs cement with 300# hulls.
POOH. Tied onto casing and pumped 30 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.
Tied onto backside and pumped 60 sxs cement with 100# hulls.
Max. P.S.I. 500#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
4004	4034		ARBUCKLE

INVOICED
DATE 1-9-07
INV. NO. 20070601105

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

Case Morris

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

DEC 26 2006


CONSERVATION DIVISION
WICHITA, KS

DEC 21 2006

PKT

6-10 MAP NO. _____ SEC. 26-12S-22W
 STATE Kansas COUNTY Trego LOC NW NE SE
 OPER Texaco, Inc. Wichita, Kansas FT/FR _____ LINE
 WELL #2 FARM V. G. Powers FT/FR _____ LINE
 POOL Ogallah ELEV 2344 GR 2346 DF 2349 KB
 CONT Murfin Drlg. Co. GEOL. _____
 CO. _____
 INT. _____

F.R. 4-30-64 SPUD 4-28-64 COMP 6-2-64
 TD 4030 FM Arb. PBTD _____
 PRODUCING FM. FROM — TO PERF W/HOLES TREATMENT
 Arb. 4004 - 34 OH 1000A
 P. Co. P. 70 BOPD - NW, Gr. 39 deg.



Completion Record

8-5/8" @325' w/225 Sx.
 5 1/2" @4004' w/110 Sx. + DV tool @1768' w/180 Sx.

Data Inc.

KB Log Tops:			
Hb	3574 -1225	Arb.	4002 -1653
Lans	3606 -1257	LTD	4030 -1681
BKC	3848 -1499		

Ø #1 (Lans) 3706-36, Rec. 30', (4' good Poro & sat) No DST's, RTD
 4033', Ran SJ Log, 5 1/2" @4004' w/110 Sx. + DV tool @1768' w/180
 Sx. RUCT, CO 4030', LTD, \$ dn, FU 250' oil/12 hrs, nat, \$ 1/2